



**Turbo Pump**  
Servicing Pfeiffer Turbo Pumps New-Used  
High-Vacuum Equipment  
www.ajvs.com

**Chemical Injection Pumps**  
B+L manufactures Chemical Injection Pumps  
for your processing needs.  
www.branluebbe.com

**KMT Waterjet Cutting**  
Easy to Use Waterjet Cutting System Longer  
Lasting and most reliable  
www.KMTWaterjet.com

Ads by Google

**COMMERCE BUSINESS DAILY ISSUE OF MARCH 30, 2001 PSA #2819  
SOLICITATIONS**

**N -- FEEDWATER PUMP**

**Notice Date**  
March 28, 2001

**Contracting Office**  
US Army ARDEC, AMSTA-AR-PC, Picatinny Arsenal, New Jersey 07806-5000

**ZIP Code**  
07806-5000

**Solicitation Number**  
DAAE30-01-Q-0604

**Response Due**  
April 19, 2001

**Point of Contact**  
Ms. J. smith, Contract Specialist,, 973-724-2623

**E-Mail Address**  
Jo Ann Smith (josmith@pica.army.mil)

**Description**

THIS IS A COMBINED SYNOPSIS/SOLICITATION FOR COMMERCIAL ITEMS PREPARED IN ACCORDANCE WITH THE FORMAT IN SUBPART 12.6, AS SUPPLEMENTED WITH ADDITIONAL INFORMATION INCLUDED IN THIS NOTICE. THIS ANNOUNCEMENT CONSTITUTES THE ONLY SOLICITATION; PROPOSALS ARE BEING REQUESTED AND A WRITTEN SOLICITATION WILL NOT BE ISSUED. SOLICITATION DAAE30-01-Q-0604 IS BEING ISSUED AS A REQUEST FOR QUOTATION (RFQ). THE SOLICITATION DOCUMENT AND INCORPORATED PROVISIONS AND CLAUSES ARE THOSE IN EFFECT THROUGH FEDERAL ACQUISITION CIRCULAR 97-23. NAICS CODE 811310, SIZE STD \$5.0 ITEM DESCRIPTION QTY U/I UNIT PRICE AMOUNT 0001 FURNISH & INSTALL 1 EA \$ \_\_\_\_\_ FEEDWATER PUMP EXISTING FEEDWATER PUMP SPECS: WORTHINGTON, 2 1/2 UNQ-10 DRIVEN BY EXISTING 150 HP MOTOR, CENTRIFUGAL, 250 GPM, 1200 TDH (MIN 1160 TDH), DEAERATED WATER SUPPLY @ MIN TEMP 225 DEGREES, 15-20 PSIG @ PUMP SUCTION, INSIDE PRESSURE 500 PSI, DISCHARGE 600 PSI, CAST IRON CONSTRUCTION, BRONZE TRIM, STD PACKING STUFFING BOX & LUBRICATED BEARINGS. EXISTING MOTOR SPECS: GENERAL ELECTRIC, INDUCTION 150 HP MOTOR DRIVE, TYPE K, FRAME 405TS, 460V, 3 PHASE, 60 CYCLE, 3560 FL RPM, SERVICE FACTOR 1.15, TIME RATING CONT. STATEMENT OF WORK: FURNISH ALL LABOR, SUPERVISION, TRAVEL, TOOLS, EQUIPMENT, SUPPLIES, SHIPPING/ HANDLING COSTS AND MATERIALS TO INSTALL EXACT FITTING FEEDWATER PUMP USING EXISTING MOTOR, PICATINNY ARSENAL NJ, POWERHOUSE, BLDG 506, ON A FIRM-FIXED- PRICE BASIS. PUMP FURNISHED SHALL BE NEW NOT REBUILT. EXISTING PUMP SHALL BE REMOVED AND PROPERLY DISPOSED OF BY THE CONTRACTOR. THE 150 HP MOTOR SHALL BE REMOVED AND SET ASIDE DURING PUMP BASE REFURBISHING. CONTRACTOR SHALL PREPARE AREA OF INSTALLATION PRIOR TO INSTALLATION OF THE NEW REPLACEMENT PUMP AND EXISTING MOTOR ASSEMBLY. PUMP BASE REINFORCEMENT AND SURFACE SHALL BE REFUR- BISHED PRIOR TO PLACEMENT OF

